

ASBESTOS MATERIALS

The following materials either tested positive or are presumed to be asbestos-containing. Materials that had mixed results are considered positive. Materials not sampled may contain asbestos and should be tested to verify asbestos content prior to impact, demolition, renovation, etc.

(+) Tested Positive, (M) Mixed Results, (P) Presumed Positive

Madras Elementary School (MES)			
Result	Material	Location	Quantity
P	Sheet Floor Covering	Faculty restroom and various classrooms	
P	Poured Terazzo Flooring	Kitchen	
P	12" x 12" Vinyl Floor Tile and Mastic	Main office and health room	
P	Wall and Ceiling Plaster	Throughout school; above lay-in ceiling tiles	
P	Carpet Mastic	Various classrooms	
P	2' x 4' Lay-in Ceiling Tile	Various hallways and classrooms	
P	9" x 9" Vinyl Floor Tile and Mastic	Various hallways and classrooms	

MATERIALS THAT TESTED NEGATIVE FOR ASBESTOS

The following materials tested negative. Although no asbestos was detected, it is possible that further sampling could indicate asbestos content. It may be prudent to test prior to impact, demolition, renovation, etc.

ASBESTOS SUMMARY

July 2021 **Project Number:** #
Activity Type: Reinspection
Activity Name: 2021 - AHERA Reinspection
Location: Throughout
Description:
Related Documents: Yes

July 2023 **Project Number:** MES2023-2
Activity Type: Periodic Surveillance
Activity Name: July 2023 Periodic Surveillance
Location: Madras Elementary School
Description:
Related Documents: Yes